

sq.m. with individual specimen shrubs. **Proposed Native Buffer Mix** Proposed mix of native shrubs along the boundaries to provide substantial buffer Planted at 3 plants per sq.m.

Proposed Wildflower Meadow WF19 Pollinators Paradise by Germinal or similar approved.

Proposed Tarmacadam for Roads

Proposed Black Tarmac for Footpaths Pink hatch indicates NO DIG construction method within RPA of existing trees. Permeable tarmac to

Proposed Concrete Tactile Paving and Drop Kerbs Detailed position of crossing to be agreed on site.


Proposed Coloured Tarmac For Circulation Paths within Residents Garden

Proposed Flag Paving for Private Patios To be Fusion modular granite aggregate paving, in Silver colour, 600x300x60mm, by Tobermore or similar approved.

Proposed Block Paving for Crossing To be Fusion modular granite aggregate paving, in Mid Grey colour, 200x100x80mm, by Tobermore or similar approved.

GENERAL NOTES

- 1. This drawing is the copyright of tpm landscape Ltd and cannot be reproduced in any form without the consent of the company This drawing is to be read in conjunction with detail landscape drawings, details and specification.
- This drawing is to be read in conjunction with all relevant Architects', Engineer's, Specialists, Bills of Quantities and Specifications.
- 4. The insertion of any firm or proprietary brand on this drawing is an indication of the class or quality required and does not exclude the use of alternative materials that are equal in performance, quality and appearance, provided that they have been approved in writing by the Landscape Architect.
- The Contractor is responsible for accurately ascertaining the position of underground services and responding to all relevant service easement requirements.
- All dimensions are in millimetres unless stated otherwise, for the purposes of construction this drawing must not be scaled and only written dimensions used. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. IF IN DOUBT PLEASE ASK.
- All work and materials are to be in accordance with the relevant British Standards and Code of Practice.
- All Proprietary products are to be used strictly in accordance with the manufacturer's instructions and details.



BOUNDARY TREATMENT

HARD LANDSCAPE / FEATURES

Proposed 1800mm Railings with Gates

Proposed 1100mm Railings



\$2,500

Proposed Low Stone Wall To the site entrance.

Proposed Levels Refer to architects drawings for levels.

> REVISION NOTES Rev By Description
> MW
> Changed in line with revised levels
> 04.06.20
>
>
> MW
> Changed in line with new layout
> 29.05.20
>
>
> MW
> Changed in line with line into moments
> 28.04.20
>
>
> MW
> Changed in line with line with rev site plan
> 28.04.20
>
>
> MW
> Retention of 157 Ash and 158 Goat Willow
> 06.03.19
>
>
> MW
> Changed in line with new layout.
> 28.02.19
> 28.02 19 02.11 18 KP Main Entrance area amendment
> KP Delivery area amendment
> MW Changed in line with new layout. 01.11 18 26.10 18 \bigcirc Fed3 Projects - HC One Knowle Lane, Cranleigh Landscape Masterplan

For Approval Scale @ A1 1:500 MW KP 23.10.18 Job number 3106 Proving number Revisior - T

> tpm landscape chartered landscape arch address: 4th Floor Studio 10 Little Lever St Manchest tel: 0161 235 0600 fax 0601 email info@tpmlands